
DESIGN DATA		
TANK NO.		T-503
QUANTITY		1
CAPACITY		30000 m^3
TANK INSIDE DIAMETER		50000 mm
TANK HEIGHT		16800 mm
HEIGHT LIQUID LEVEL		15300 mm
LOW LIQUID LEVEL		750 mm
CONTENTS	NAME	GAS OIL/PREMIUM
	FLASH POINT	HOLD
	MAX OPER. TEMP.	60 C°
	SPECIFIC GRAVITY	0.74 (MAX 1.04) TEST WATER
DESIGN CODE		API 650 10 ED ADD 3 2003 W/APP E&C
OPERATING PRESSURE		ATMOSPHERIC
DESIGN METAL TEMPERATURE		90 C°
DESIGN PRESSURE		ATMOSPHERIC
PUMPING RATE	IN	HOLD
	OUT	HOLD
CORR.ALLOWANCE	SHELL	1.5 mm
	BOTTOM	1.5 mm
	ROOF	1.5 mm
	STRUCTURAL	0 mm
SHELL DESIGN		API 650, ONE FOOT METHODE
ROOF TYPE		FLOATING ROOF (PONTOON TYPE)
BOTTOM SLOPE		1:60 (FROM CENTER)
DESIGN EARTHQUAKE FACTOR		API 650, APP.E ZONE 2A
DESIGN WIND SPEED		150 km/h
DESIGN RAINFALL		HOLD
INTERNAL COATING		---
PAINTING	EXTERIOR	YES
	INTERIOR	YES (BOTTOM+1 m LOWER&UPPER SHELL)
	BOTTOM UNDERSIDE	YES (EPOXY TAR COATING)
INSULATION		NO

ACCESSORIES			
NO	ITEM NAME	QT'Y	REMARKS
1	SPIRAL STAIRWAY	1 SET	WITH TOP PLATFORM
2	ROLLING LADDER	1 SET	
3	WIND GIRDER HANDRAIL	1 SET	ALL CIRCUMFERENCE OF TANK
4	ROOF DRAIN	1 SET	
5	ROOF EARTH LUG	HOLD	
6	TANK EARTH LUG	12	
7	NAME PLATE	1 SET	
8	AIR FOAM SYSTEM	1 SET	
9	WATER SPRAY SYSTEM	1 SET	
10	LEVEL GAUGE SYSTEM	1 SET	

MATERIAL LIST	
SHELL PLATE	A 573-70
ANNULUR PLATE	A 573-70
BOTTOM PLATE	A 573-70
DECK PLATE	A 573-70
PONTOON PLATE	A 573-70
TOP ANGLE	S 235 JR G2
STRUCTURAL	S 235 JR G2
NOZZLE NECK	API 5L Gr B
NOZZLE FLANGE	A 105
GASKET	NON COMPRESSED ASBESTOS
BOLT & NUT	A 307
EARTHING LUG	SS 304
NAME PLATE	SS 304

N O T E S

1. UNLESS OTHERWISE NOTED, ALL MEASUREMENT ARE IN MILLIMETERS.
2. NOZZLE LOCATION ARE INDICATIVE ONLY, ORIENTATION AND ELEVATION REFER TO DRAWING 02001-2-60-DG-0002 "ORIENTATION".
3. HOLD ITEM WILL BE COMPLETED DURING DETAIL ENGINEERING.
4. THE PLATE THICKNESS SHOWN IN THE DRAWING ARE MINIMUM THICKNESS, VENDOR SHALL CHECK AND SPECIFY THICKNESS IN ACCORDANCE WITH CODE AND OTHER REQUISITION REQUIREMENT.
5. REQUIRED NUMBER OF FOAM CHAMBER SHALL BE CHECKED BY PROCESS/PLANT SERVICESS ENGINEER.
6. FIRE WATER SPRAY SYSTEM SHALL BE VERIFY BY PLANT SERVICES ENGINEER. QUANTITY AND DESIGN FOR SPRAY NOZZLE SHALL BE PREPARED BY PLANT SERVICES.
7. ALL BOLT HOLES FOR MANHOLES AND NOZZLES SHALL BE STRADLE TO CENTERLINE NORTH.



GENERAL ARRANGEMENT